



Administrative Services

Purchasing Division

CITY OF FORT COLLINS

ADDENDUM No. 1

BID #5696

SOUTH SHIELDS STREET IMPROVEMENTS

SPECIFICATIONS AND CONTRACT DOCUMENTS

Description of Bid #5696 South Shields Street Improvements

OPENING DATE: April 16, 2002, 3:00p.m. (Our Clock)

To all prospective bidders under the specifications and contract documents described above, the following changes are hereby made.

I. **Bid item clarifications:** The highlighted items are the changes that have been made.

210-04	Adjust Manhole Ring/Cover	10	EA
304-03	Aggregate Base Course – (CI 5 or 6) – 6" Depth – (CIP)	225	TON
403-07	Asphalt Hand Patching – Grading SG PG 64-22 Binder	55	TON
608-08	Concrete Sidewalk 7' (Thickness = 6")	2325	SF
608-10	Concrete Crossspan and Aprons (Thickness = 8")	250	SF
608-11	Concrete Sidewalk (Various Widths) – (Thickness = 4")	1000	SF
2810-02	Sprinkler Line Install	300	LF

NOTE: Attached is a new Bid Schedule that reflects the above changes. Please disregard the previous Bid Schedule and use the attached in it's place.

II. **Item Description Clarification:**

- Roll-Over Curb and Gutter – This item includes curb and gutter and sidewalk that has been monolithically poured
- **630-03 Night Time Traffic Control** – This item will cover the weekend closures that will be necessary to mill and overlay the Prospect and Shields Intersection and will be paid for as a lump sum price.
- Landscaping Maintenance – This item (as defined in the specifications) has a warranty period of 2 years. During the 2 year warranty, the landscaper will be required to mow and keep the parkway clean until final acceptance.
- Orange 4' Safety fence with T-Posts (Approx. 300 feet) shall be installed along the staging area during construction.

If you have any questions please contact John Stephen, CPPB, Senior Buyer, at 970-221-6777.

RECEIPT OF THIS ADDENDUM MUST BE ACKNOWLEDGED BY A WRITTEN STATEMENT ENCLOSED WITH THE BID/QUOTE STATING THAT THIS ADDENDUM HAS BEEN RECEIVED.

Project: South Shields Street Improvement Project ADDENDUM #1

Spec/Item Number	Description	Estimated Quantity	Unit	Unit Cost	Item Cost
South Shields Street Quantities:					
202-01	Remove Vertical Curb & Gutter	285	LF		
202-02	Remove Crossspan, Apron, Driveway	860	SF		
202-03	Remove Roll Over Curb	160	SF		
202-04	Remove Asphalt 5"-8" thick	7,390	SY		
202-05	Remove Sidewalk	8,295	SF		
202-06	Remove Concrete Light Pole Bases (Top 3') and Haul	3	EA		
202-07	Remove Existing Inlets Type R 5'	2	EA		
202-08	Remove Tree Stump (Avg. Width = 48" Diameter)	1	EA		
202-09	Remove Landscape Boulders (Corner of Stuart and Shields - approx. 4"-8" cobbles)	1	LS		
203-01	Unclassified Excavation	2,350	CY		
203-02	Embankment (CIP)	2,020	CY		
203-03	Borrow- Suitable Fill Material (Unforeseen Circumstances Only)	577	CY		
203-04	Haul and Dispose	330	CY		
203-05	Muck Excavation (CIP)	275	CY		
203-06	Borrow ABC (cl 5 or 6) CIP	385	TON		
203-07	Topsoil (stripping, stockpile, placing)	730	CY		
203-08	Swale Grading	615	LF		
203-09	Potholing	1	LS		
208-01	Erosion Control	1	LS		
210-01	Adjust Manhole Ring/Cover	5	EA		
210-02	Modify Manhole	2	EA		
210-03	Adjust Valve Box	4	EA		
304-01	Aggregate Base Course - (CI 5 or 6) - 6" Depth - (CIP)	3,180	TON		
304-02	Aggregate Base Course Patch Placement - (CI 5 or 6) - 6" Depth - (CIP)	200	TON		
306-01	Reconditioning (8")	2,435	SY		
307-01	Flyash Subgrade Stabilization (12%)	7,300	SY		
403-01	Hot Bituminous Pavement - Grading S (4" Depth) (PG 78-28)	2,430	TON		
403-02	Hot Bituminous Pavement - Grading SG (6" Depth) (PG 64-22)	3,180	TON		
403-03	Asphalt Paver Patching - Grading S (4" Depth) PG 64-22 Binder	100	TON		
403-04	Asphalt Paver Patching - Grading SG (7" Depth) PG 64-22 Binder	150	TON		
412-01	Portland Cement Concrete Pavement (10" Depth)	260	SY		
420-01	Mirafi Filter Material	800	SY		
506-01	15"x20"X1.5' Class 12 Rip-Rap with 6" topsoil (CIP per detail)	33	SY		
506-02	5'x5'X1.5' Class 12 Rip-Rap with 6" topsoil (CIP per detail)	6	SY		
603-01	4" PVC Schedule 200 Irrigation Sleeving	100	LF		
604-01	5' Type R Inlet	1	EA		
604-02	Combination Type 13 Inlet	1	EA		
608-01	Concrete Sidewalk 7" (Thickness = 6")	9,000	SF		
608-02	Concrete Access Ramps with Colored Landings (Thickness = 6")	1,860	SF		
608-03	Concrete Crossspan and Aprons (Thickness = 10")	900	SF		
608-04	Concrete Bus Pad (Thickness = 6")	250	SF		
608-05	Patterened Asphalt Crosswalks	3,000	SF		
608-06	Hi Early Concrete	75	CY		
608-07	Flow Fill	150	CY		
609-01	Vertical Curb and Gutter	1,200	LF		
609-02	Roll-Over Curb and Gutter	100	LF		
619-01	8"x 2" Plug and Blow Off	1	EA		
619-02	30"x8" Tapping Saddle (FC Spec)	1	EA		
619-03	8" Taping Valve and Connection	1	EA		
619-04	8" DIP with Poly Wrap	40	LF		
619-05	Install 72" Valve Manhole over Existing 30"	1	EA		
619-06	Irrigation Service (3/4") - City of Fort Collins Spec	1	EA		

Subtotal South Shields Street Quantities:

\$ _____

Pavement Management - Street Rehabilitation Quantities:

202-10	Rotomill Asphalt (Avg. Depth = 4")	12,000.0	SY	_____	_____
202-11	Remove Glue-down Curb & Gutter with Hardscape	1.0	LS	_____	_____
202-12	Remove Vertical Curb & Gutter	685	LF	_____	_____
202-13	Remove Crossspan, Apron, Driveway	610	SF	_____	_____
202-14	Remove Roll Over Curb and Gutter	90	LF	_____	_____
202-15	Remove Asphalt Pavement (5"-8" thick)	2,000	SY	_____	_____
202-16	Remove Sidewalk	3,225	SF	_____	_____
202-17	Cap off Irrigation / Sprinkler	4	EA	_____	_____
203-10	Unclassified Excavation	60	CY	_____	_____
203-11	Embankment	60	CY	_____	_____
203-12	Borrow ABC (cl 5 or 6) CIP	130	TON	_____	_____
210-04	Adjust Manhole Ring/Cover	10	EA	_____	_____
210-05	Adjust Valve Box	7	EA	_____	_____
304-03	Aggregate Base Course - (Cl 5 or 6) - 6" Depth - (CIP)	225	TON	_____	_____
403-05	Hot Bituminous Pavement - Grading S (4" Depth) (PG 76-28)	3,000	TON	_____	_____
403-06	Hot Bituminous Pavement - Grading SG (6" Depth) (PG 64-22)	275	TON	_____	_____
403-07	Asphalt Hand Patching - Grading SG PG 64-22 Binder	55	TON	_____	_____
608-08	Concrete Sidewalk 7' (Thickness = 6")	2,325	SF	_____	_____
608-09	Concrete Access Ramps with Colored Landings (Thickness = 6")	360	SF	_____	_____
608-10	Concrete Crossspan and Aprons (Thickness = 6")	250	SF	_____	_____
608-11	Concrete Sidewalk (Various Widths) - (Thickness = 4")	1,000	SF	_____	_____
609-03	Vertical Curb and Gutter	625	LF	_____	_____
609-04	Roll-Over Curb and Gutter	180	LF	_____	_____

Subtotal Pavement Management - Rehabilitation Quantities: \$ _____

Landscaping Quantities:

2810-01	Irrigation	1.0	LS	_____	_____
2810-02	Sprinkler Line Install	300	LF	_____	_____
2900-01	Burr Oak - 2" Caliper B&B	38	EA	_____	_____
2900-02	Import Topsoil (Screened - 3" Depth) - (BOC) - (CIP)	300	CY	_____	_____
2900-03	Turf Sod	2,700	SF	_____	_____
2900-04	Sod Prep Replacement	1,300	SY	_____	_____

Subtotal Landscaping Quantities: \$ _____

Miscellaneous Quantities:

-	Contract Bond			_____	_____
625-01	Construction Surveying			_____	_____
626-01	Mobilization			_____	_____
630-01	Type III Barricades			_____	_____
630-02	Traffic Control			_____	_____
630-03	Night Time Traffic Control			_____	_____

Subtotal Misc. Quantities: \$ _____

TOTAL CONSTRUCTION COST = \$ _____

IN WORDS: _____